

Articles of Agreement

Made and entered into between Pittsburgh Art Glass Co.
party of the first part, and the Building Committee
representing the Tree of Life Synagogue Mountaintown Pa
party of the second part:

Witnesseth, That for the consideration hereinafter mentioned, the said party of the first part contracts to furnish to the said party of the second part the stained and ornamental glass for the above named building, for the sum of \$ 1900.00 installed in Building.
f. o. b. factory

The party of the first part using such colors and drawings as in his judgment, will produce the most artistic results and to have all ready for delivery on or about January 15th 1925

Windows having no sash the party of the first part will set directly into frames at the building ready for the carpenter to put on the stops. All necessary carpenter work and scaffolding to be furnished by the party of the second part.

The windows to be made according to the following specifications, and similar to designs herein mentioned:

Twelve large windows to be made after design #2141. Each to have a different emblem. 7 of these to have two ventilators each and two to have one ventilator each. One large window in front of building to be made after design #2143. A small picture of a tree to be placed within the stars shown on this design with appropriate Hebrew lettering. Four small windows in front of building to be made after design #2142. Four small windows in the rear of building to harmonize in design and color with other windows. Inscriptions extra at \$3.00 each up to 25 letters. Extra letters 15¢ each.

The materials to be used in the construction of this work shall be: Best Opalescent Glassware Throughout.

The work shall be performed in a workmanlike manner, and provided with: Our Patented Bulge Proof Brass Bar

This contract is made with the explicit understanding that the party of the first part is not responsible for any delays caused by strikes, accidents, or other causes beyond his control.

It is also understood that this agreement expresses the whole contract, and that there are no understandings or oral agreements of any kind, not herein contained.

In consideration of the fulfillment of this contract by the party of the first part, the parties of the second part bind themselves to pay unto the parties of the first part the net sum of \$ 1900.00 25 per cent of the above amount to be paid when work is begun on the windows, 50 per cent of the amount to be paid in cash on delivery of invoice with bill of lading attached and the remainder within thirty (30) days after the arrival of the windows. are installed.

For any part of the work which may be damaged in transit or which is in dispute, its value only can be withheld from payments as agreed upon until it has been repaired or settled.

Witness, our hands and seals this 26th day of November, A. D. 1924

Executed in presence of

Louis [Signature]

PITTSBURGH ART GLASS CO.

Howard S. Gilbert
Clyde [Signature]
[Signature]

